

FUNCTIONAL SERVICING REPORT

In Support of Site Plan Approval



Taunton Road and Burkholder Drive City of Pickering Proposed Commercial Development

Report Prepared for:

Seaton Commercial Developments Ltd.
5400 Young St., Suite 300
North York, Ontario
M2N 5R5

Report Prepared by:

2453 Auckland Drive
Burlington, Ontario
L7L 7A9

TABLE OF CONTENTS

1.0	Introduction	1
2.0	Background Information	1
3.0	Sanitary Demand.....	1
	3.1 Existing Sanitary Servicing	1
	3.2 Proposed Sanitary Servicing	2
	3.2.1 Sanitary Flow.....	2
	3.2.2 Connection and Layout	2
4.0	Water Demand	2
	4.1 Existing Water Servicing.....	2
	4.2 Proposed Water Servicing.....	3
	4.2.1 Domestic Demand	3
	4.2.2 Fire Demand.....	5
	4.2.3 Connection and Layout	5
5.0	Conclusion.....	5

List of Tables

- Table 1: Expected Peak Sanitary Discharge by Building
- Table 2: Expected Water Demand by Land Use (Avg. Daily Demand)
- Table 3: Peaking Factors (MOE Table 3-3, 2008)
- Table 4: Expected Peak Water Demand by Land Use (Maximum Hour & Maximum Day)
- Table 5: Expected Peak Water Demand (Maximum Hour & Maximum Day)

List of Appendices

- Appendix A – Sanitary Drainage Plan and Demand Calculations
- Appendix B – Watermain Pressure Zones and Demand Calculations
- Appendix C – Drawings

List of Drawings

- SGP – Site Grading Plan
- SSP – Site Servicing Plan
- ESC - 1 – Erosion and Sediment Control Plan 1
- ESC - 2 – Erosion and Sediment Control Plan 2
- CMP – Construction Management Plan
- SDP - 1 – Site Details Plan 1
- SDP - 2 – Site Details Plan 2
- XSEC – Chamber Cross Sections

1.0 INTRODUCTION

KWA Site Development Consulting Inc. (“KWA”) has been retained by Seaton Commercial Developments Ltd. (“Client”) to prepare this Functional Servicing Report in support of a Site Plan Approval (“SPA”) for the commercial development located at Taunton Road and Burkholder Drive in the City of Pickering, Ontario.

The area that is subject to this application (herein the “site”) is approximately 6.08 hectares (ha) and is located within Block 76 and a portion of Block 188 of the Taunton Road and Taunton Road West Subdivision. The site is part of the Duffins Creek Watershed. Generally, the site is sloped northwest to southeast with elevations ranging from 176 m (in the northwest corner) to 167 m (in the southeast corner). The Trans-Northern Pipeline (TNP) Easement is located along the south boundary with Marathon Avenue and is approximately 18 m wide and 0.44 ha in area. There is also approximately 0.16 ha of site area located southwest of the TNP Easement. A private right-of-way, approximately 0.39 ha in area, is proposed along the eastern perimeter and provides connection to Taunton Road and Marathon Avenue. In addition, two other access points are proposed: one from Burkholder Drive and another from Taunton Road.

Surrounding land uses include:

- Taunton Road to the north,
- Private right-of-way (ROW) to the east,
- Marathon Avenue to the south and,
- Burkholder Drive to the west.

The site plan proposes seven (7) commercial buildings. There will be approximately 643 on-site parking spaces. Refer to the **Site Plan (A100)** developed by GetReal Architectural Services.

2.0 BACKGROUND INFORMATION

This Servicing Brief has been prepared in coordination and regarding the following documents and drawings:

- Architectural Site Plan prepared by GetReal Architectural Services (received Dec 2, 2025)
- Topographic Survey by J.D.Barnes Ltd (dated July 28, 2025)
- The Regional Municipality of Durham Design Specifications for Watermains, dated April 2020
- The Regional Municipality of Durham Design Specifications for Sanitary Sewers, dated April 2020
- Ministry of Environment’s Design Guidelines for Drinking Water Systems, dated 2008
- Ministry of Environment’s Design Guidelines for Sewage Works, dated 2008

3.0 SANITARY DEMAND

3.1 EXISTING SANITARY SERVICING

There is an existing manhole MH-L6-132 with an associated 200 mm diameter sanitary service for Block 76. The sewer is sloped at 1.28% to MH-L6-130 located in Marathon Avenue. Refer to **Appendix A** for the as-constructed drawing of Marathon Avenue sanitary sewers from Station 0+000 and Station 0+227.65 prepared by GEI for Lebovic Enterprises Ltd (SP-2009-14) that shows the provided sanitary service connection from the site to Marathon Avenue. The sanitary sewer flows east on Marathon Avenue via a network of sewers within the Taunton Road and Taunton Road West Subdivision. The sanitary ultimately meets the 900 mm diameter concrete trunk sewer at the intersection of Marathon Avenue and Aquarius Trail.

The existing sanitary allowance for the subject site is based on the **Sanitary Drainage Plan, Drawing 301** prepared by Cole Engineering for 1133373 Ontario Inc. (SP-2008-07), see **Appendix A**. Based on the 4.82 ha area for Block 76, an allowance of **5.02 L/s** is provided to the Marathon Avenue sanitary sewer.

3.2 PROPOSED SANITARY SERVICING

This section of the report details the proposed sanitary flow, servicing connection and layout.

3.2.1 SANITARY FLOW

Based on the latest Region of Durham sanitary design standards (2020), the design flow for commercial properties is 180m³/gross floor area ha/day (2.08 L/s/ha). This design flow rate includes infiltration and peaking effect. The sanitary flows for each building are outlined in **Table 1** below. Refer to the Site Plan (**A100 SP19**) for building I.D.'s.

Table 1: Expected Peak Sanitary Discharge by Building

Building ID	Building Footprint (m ²)	Peak Sanitary Flow (L/s)
A1	3985	0.83
A2	611	0.13
A3	979	0.20
A4	1587	0.33
B	1117	0.23
C	725	0.15
D	650	0.14
E	845	0.18
F	1368	0.29
G	557	0.12
TOTAL	12,424	2.59

The sanitary demand is estimated to be **2.59 L/s**, including peaking factor and extraneous flows. This value is less than 5.02 L/s and therefore within the allowable limit as defined by the subdivision **Sanitary Drainage Plan, Drawing 301** prepared by Cole Engineering. Refer to **Appendix A** for **Sanitary Demand Calculations**.

3.2.2 CONNECTION AND LAYOUT

The proposed buildings will each outlet sanitary flows to a network of 200 mm diameter sanitary sewers within the subject site. Sanitary flows will drain to MH-L6-74 on Marathon Avenue, which has approximately 167 m downstream of the existing sanitary connection provided for the site.

Refer to the **Site Servicing Plan** in **Appendix C**.

4.0 WATER DEMAND

4.1 EXISTING WATER SERVICING

The existing 150 mm diameter domestic and 200 mm diameter fire service for Block 76 is located to the south and connects into the existing 300mm diameter watermain in the northern boulevard of Marathon Avenue. There is no watermain infrastructure within the subject site boundaries, and the site is located within pressure zone 4 based on the **Watermain Pressure Zone Plan, Drawing 105** prepared by Cole Engineering for 1133373 Ontario Inc. (SP-2008-07), see **Appendix B**.

4.2 PROPOSED WATER SERVICING

This section of the report details the proposed water demand, servicing connection and layout.

4.2.1 DOMESTIC DEMAND

According to The Region of Durham standards, there are two ways of calculating water demands for a commercial area: by average daily consumption per land use or on a per capita basis.

There are guidelines for commercial water demands specified in the Region of Durham's Design Specifications for Watermains. The average daily consumption rate for shopping centers is provided to be 2500 - 5000 L/day/1000 m². This aligns with the rates listed in the Ministry of Environment's Table 3-2 Typical Water Demands for Selected Commercial and Institutional Users.

Assuming the conservative rate of 5 L/d/m², the domestic demand for each building is outlined in **Table 2** below. Note, the proposed development consists of seven (7) commercial buildings, labelled 'A' through 'G'. Refer to the Site Plan (**A100 SP19**) for building I.D.'s.

Table 2: Expected Water Demand by Land Use (Avg. Daily Demand)

Building ID	Building Footprint (m ²)	Water Use (L/d/m ²)	Area Flow (L/s)
A1	3985	5	0.23
A2	611	5	0.04
A3	979	5	0.06
A4	1587	5	0.09
B	1117	5	0.06
C	725	5	0.04
D	650	5	0.04
E	845	5	0.05
F	1368	5	0.08
G	557	5	0.03
TOTAL	12,424		0.72

On a per capita basis, the equivalent population for the development is determined. The Region's Design Specifications suggest that a population equivalent of 86 persons per hectare shall be used. Based on a commercial development area of 6.08 ha, the equivalent population is as follows:

$$\text{Equivalent Population} = 86 \text{ persons/ha} \times 6.08 \text{ ha} = 523 \text{ people}$$

Though the Region of Durham standards do not provide a design flow for commercial developments, it is understood through previous development applications that the sanitary per capita rate of 364 L/cap/day applies. Accordingly, the site would have an expected water demand of:

$$Q = 364 \text{ L/cap/day} \times 523 \text{ people} = 2.20 \text{ L/s}$$

Therefore, the expected domestic water demand from the development is expected to be between **0.72** and **2.20 L/s**.

To determine the maximum hour and maximum day demands, a peaking factor must be applied. In lieu of a Region of Durham peaking factor, the Ministry of Environment Table 3-1 Peaking Factors were used. This table applies to Drinking-water systems servicing more than 500 people (refer to excerpt below).

Table 3: Peaking Factors (MOE Table 3-1, 2008)

POPULATION	MINIMUM RATE FACTOR (MINIMUM HOUR)	MAXIMUM DAY FACTOR	PEAK RATE FACTOR (PEAK HOUR)
500 - 1 000	0.40	2.75	4.13

Using the maximum day factor of 2.75 and maximum hour factor of 4.13, the flows for the site using the analysis per average daily consumption per land use are presented in **Table 4** below.

Table 4: Expected Peak Water Demand by Land Use (Maximum Hour & Maximum Day)

Building ID	Area Flow (L/s)	Maximum Day (L/s)	Maximum Hour (L/s)
A1	0.23	0.63	0.95
A2	0.04	0.10	0.15
A3	0.06	0.16	0.23
B	0.09	0.25	0.38
C	0.06	0.18	0.27
D	0.04	0.12	0.17
E	0.04	0.10	0.16
F	0.05	0.13	0.20
G	0.08	0.22	0.33
H	0.03	0.09	0.13
TOTAL	0.72	1.98	2.97

On a per capita basis, the peaking factors for the development are determined as follows:

$$\text{Maximum Day (L/s)} = 2.20 \text{ L/s} \times 2.75 = 6.06 \text{ L/s}$$

$$\text{Maximum Hour (L/s)} = 2.20 \text{ L/s} \times 4.13 = 9.10 \text{ L/s}$$

Table 5 below summarizes and compares the expected peak water demand for both analysis per average daily consumption per land use and analysis per capita.

Table 5: Expected Peak Water Demand (Maximum Hour & Maximum Day)

Condition	Area Flows (L/s)	Maximum Day (L/s)	Maximum Hour (L/s)
Analysis per Avg. Daily Consumption per Land Use	0.72	1.98	2.97
Analysis per Capita	2.20	6.06	9.10

Analysis per capita results in the highest domestic usage rate with the maximum day demand estimated to be **6.06 L/s** and the maximum hour demand estimated to be **9.10 L/s**.

Refer to **Appendix B** for **Water Demand Calculations**.

4.2.2 FIRE DEMAND

In accordance with Region standards, fire flow demands are determined using the Fire Underwriters Survey 2020 Methodology. Of the buildings on-site, Building A has the highest demand: **83.33 L/s**. This is based on the following inputs:

- NBC Occupancy 'E'
- Construction class: Non-combustible with protected vertical openings
- A fully supervised NFPA 13 compliant Sprinkler system
- Limited Combustible contents factor
- Applicable exposure charges based on distance to adjacent buildings.
- A fire wall with 2hr rating is provided between Building A1 and A2

As per MOE Drinking-Water Guidelines, it is typical to present the total demand for a development as the greater of:

- Maximum day demand plus fire flow, or
- Peak hour demand.

Therefore, the overall water demand for the development is maximum day plus fire flow, **89.39 L/s** (83.33 L/s + 6.06 L/s).

Refer to **Appendix B** for **Fire Flow Calculations**.

4.2.3 CONNECTION AND LAYOUT

As per the **Watermain Pressure Zone Plan, Drawing 105** by Cole Engineering, the site is located within the Zone 4 water supply system for the City of Pickering.

The Site will be serviced by the existing 300mm watermain on Marathon Avenue. The existing 150 mm domestic and 200 mm fire service connections for the site will be utilized. These services will feed into a Region water meter room in Building A4 before exiting the building to service the other proposed buildings. A metering device and backflow preventer will be installed within the meter room as per Regional Specifications and Standards. Three (3) new hydrants are proposed within the proposed development to provide fire protection coverage as per NFPA and OBC guidelines. The firemain within the subject site is looped internally to provide a greater level of service and reduce pressure losses found in dead-end watermains. The proposed watermain layout can be seen on the **Site Servicing Plan** in **Appendix C**.

5.0 CONCLUSION

In summary:

Sanitary Demand:

- Based on a sanitary demand factor of 2.08 L/s/ha of commercial floor area, the sanitary demand is estimated to be **2.59 L/s**.
- The site sanitary flows will outlet from the proposed development to MH-L6-74 on Marathon Avenue.

Watermain Demand:

- Using an equivalent population of **523 people**, the water supply demand for the Site is as follows:
 - Average Daily Demand = **2.02 L/s**
 - Max Daily Demand = **6.06 L/s**
 - Peak Hour Demand = **9.10 L/s**
- The overall water demand for the development is maximum day plus fire flow, **89.39 L/s**.
- The Site will be serviced by two existing connections (100 mm domestic and 200 mm fire) to the existing 300mm watermain on Marathon Avenue.

- A metering device and backflow preventer will be installed within the meter room in Building A4 as per Regional Specifications and Standards. Three (3) new hydrants are proposed within the proposed development to provide fire protection coverage as per NFPA and OBC guidelines.

We trust that this report sufficiently addresses the site servicing requirements and that the proposed development is feasible from a municipal servicing perspective.

Please do not hesitate to contact the undersigned if you have any questions or concerns.

Yours very truly,

KWA Site Development Consulting Inc.



Per:

Ben Jackson, P.Eng.

(416)-984-0970


Pavneet Brar, P.Eng., MASC

(289)-259-3545


APPENDIX A

Sanitary Drainage Plan and Demand Calculations

SEE DWG. 304



SEE DWG. 302



KEYPLAN N.T.S.

- LEGEND**
- EXISTING SANITARY MANHOLE
 - PROPOSED SANITARY MANHOLE
 - PROPOSED SANITARY SEWER
 - PROPOSED SANITARY DRAINAGE AREA BOUNDARY
 - - - - EXISTING SANITARY DRAINAGE AREA BOUNDARY
 - PROP. DRAINAGE AREA (ha)
 - POPULATION
 - # OF UNITS
 - 84 85 PROPOSED LOT NUMBERS
 - PROPOSED DRIVEWAY LOCATION
 - SANITARY SERVICE CONNECTION (TYP.)
 - BOUNDARY LIMIT

REFER TO DRAWING No.100 FOR GENERAL NOTES

BENCHMARK
 ELEVATIONS HEREON ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING BENCHMARK No. 2-045, HAVING A PUBLISHED ELEVATION OF 126.055m (CGVD-1928:1978). BRASS TABLET SET HORIZONTALLY IN SOUTH FACE OF BRICK BUILDING, LOCATED 650mS. WEST OF VALLEY ROAD AND 34mS. NORTH OF THE CENTERLINE OF THIRD CONCESSION ROAD. TABLET IS LOCATED 0.47m WEST OF THE SOUTHEAST CORNER OF BUILDING AND IS 0.52m ABOVE GROUND LEVEL.

No.	DESCRIPTION	DATE	BY
2	UPDATED SANITARY SEWER DESIGN	03/20/18	L.A.B.
1	ISSUED FOR CONSTRUCTION	12/20/17	A.R.

THE CORPORATION OF THE CITY OF PICKERING
 Engineering Services Department

APPROVED
 Approval of the Regional Works Dept. for the purposes described in the applicable Regional Subdivision or Servicing Agreement. The Region is relying on the technical skill and ability of the P. Eng. sealing and signing this drawing.
 By: PAUL ALLEN
 Date: DEC. 20, 2017

1133373 ONTARIO INC.
 (SP-2008-07)

SANITARY DRAINAGE PLAN



DESIGN BY: A.L.	DRAWN BY: T.L.	PROJECT No. LD12-0605
SCALE: 1:1000	DATE: MARCH 2015	DRAWING No. 301

Sanitary Demand

Project Name: Fieldgate Seaton
Project Number: 23810
Location: Seaton, ON
Date: 12/1/2025
Prepared by: PB

Total Site Area 6.08 ha

Water Demands using Average Daily Consumption per Land Use

Flow Data			
Building ID	Building Area (m ²)	Water use (Daily Average) (L/d.m ²) ²	Area Flow (L/s)
A1	3985	18	0.83
A2	611	18	0.13
A3	979	18	0.20
A4	1587	18	0.33
B	1117	18	0.23
C	725	18	0.15
D	650	18	0.14
E	845	18	0.18
F	1368	18	0.29
G	557	18	0.12
Total	12424		2.59

APPENDIX B

Watermain Pressure Zones and Demand Calculations

Domestic Water Demand

Project Name: Fieldgate Seaton
Project Number: 23810
Location: Seaton, ON
Date: 12/1/2025
Prepared by: PB

Total Site Area 6.08 ha

Water Demands using Average Daily Consumption per Land Use

Flow Data			
Building ID	Building Area (m ²)	Water use (Daily Average) (L/d.m ²) ²	Area Flow (L/s)
A1	3985	5	0.23
A2	611	5	0.04
A3	979	5	0.06
A4	1587	5	0.09
B	1117	5	0.06
C	725	5	0.04
D	650	5	0.04
E	845	5	0.05
F	1368	5	0.08
G	557	5	0.03
TOTAL	12424		0.72

Population Density 86 people/ ha
Population 523 people

Water Demands using per Capita Consumption

Region's per capita average consumption 364 Lcpd
Water Demand 2.20 L/s

MOE Table 3-1 (2008 Design Guidelines for Drinking-Water Systems) Peaking Factors for Drinking Water Systems Serving More than 500 People

POPULATION	MINIMUM RATE FACTOR (MINIMUM HOUR)	MAXIMUM DAY FACTOR	PEAK RATE FACTOR (PEAK HOUR)
500 - 1 000	0.40	2.75	4.13

MOE Peaking Factors

Max Day Factor	2.75
Peak Hour Factor	4.13

Water Demands using Average Daily Consumption per Land Use (with MOE Peaking Factors)

Building ID	Area Flow (L/s)	Maximum Day (L/s)	Maximum Hour (L/s)
A1	0.23	0.63	0.95
A2	0.04	0.10	0.15
A3	0.06	0.16	0.23
A4	0.09	0.25	0.38
B	0.06	0.18	0.27
C	0.04	0.12	0.17
D	0.04	0.10	0.16
E	0.05	0.13	0.20
F	0.08	0.22	0.33
G	0.03	0.09	0.13
TOTAL	0.72	1.98	2.97

Water Demands using per Capita Consumption (with MOE Peaking Factors)

	Area Flow (L/s)	Maximum Day (L/s)	Maximum Hour (L/s)
Total Site	2.20	6.06	9.10

Fire Underwriters Survey - Fire Demand Calculations

Project Name: **Fieldgate Seaton Commercial**
 Project Number: **23810**
 Location: **Pickering, ON**
 Date: **4-Dec-25**
 Prepared By: **PB**

Guide for Determination of Required Flow Copyright I.S.O.

Building	Building Information				System Type										Occupancy / Contents Information		Exposure Charge								Unadjusted Flow (F=220C√A)		Correction Factors				Required Flow							
	NBC Occupancy	Footprint Area (m ²)	# of Storeys ¹	Additional Area(s) (m ²)	Construction Class	NFPA 13 Sprinkler	Credit	Standard Water Supply	Credit	Fully Supervised	Credit	Total Credits	Contents Factor	Contents Charge	East		West		North		South		Total Charge (Maximum 75%) ³	Building Contiguous	Fire Resistive Min 2 Hr Rating ²	C	K (m ²)	F (L/min) ⁴	Occupancy / Contents	Flow Adjusted for Occupancy / Contents	Sprinkler Decrease	Exposure Charge	L/min	L/s				
															Distance (m)	-H (ft) ²	Change	Distance (m)	-H (ft) ²	Change	Distance (m)	-H (ft) ²													Change	Distance (m)	-H (ft) ²	Change
A1	E	3985	1	0	NC	YES	30%	YES	10%	YES	10%	50%	LC	-15%	over 45	over 100	0%	0 to 3	over 100	5%	over 45	over 100	0%	over 45	over 100	0%	5%	NO	YES	0.8	3985	11000	-1650	9350	4675	5%	5000	83.33
A2, A3, A4	E	3177	1	0	NC	YES	30%	YES	10%	YES	10%	50%	LC	-15%	0 to 3	over 100	5%	over 45	over 100	0%	over 45	over 100	0%	over 45	over 100	0%	5%	NO	YES	0.8	3177	10000	-1500	8500	4250	5%	5000	83.33
B	E	1117	1	0	NC	YES	30%	YES	10%	YES	10%	50%	LC	-15%	over 45	over 100	0%	over 45	over 100	0%	3.1 to 10	61 to 80	2%	over 45	61 to 80	0%	2%	NO	YES	0.8	1117	6000	-900	5100	2550	2%	3000	50.00
C	E	725	1	0	NC	NO	0%	YES	0%	NO	0%	0%	LC	-15%	over 45	over 100	0%	over 45	over 100	0%	over 45	61 to 80	0%	over 45	61 to 80	0%	2%	NO	YES	0.8	725	5000	-750	4250	0	2%	4000	66.67
D	E	650	1	0	NC	NO	0%	YES	0%	NO	0%	0%	LC	-15%	3.1 to 10	61 to 80	2%	over 45	61 to 80	0%	over 45	over 100	0%	over 45	over 100	0%	2%	NO	YES	0.8	650	4000	-600	3400	0	2%	3000	50.00
E	E	845	1	0	NC	NO	0%	YES	0%	NO	0%	0%	LC	-15%	20.1 to 30	61 to 80	0%	3.1 to 10	61 to 80	2%	over 45	over 100	0%	over 45	over 100	0%	2%	NO	YES	0.8	845	5000	-750	4250	0	2%	4000	66.67
F	E	1368	1	0	NC	YES	30%	YES	10%	YES	10%	50%	LC	-15%	10.1 to 20	61 to 80	1%	20.1 to 30	61 to 80	0%	over 45	over 100	0%	over 45	over 100	0%	1%	NO	YES	0.8	1368	7000	-1050	5950	2975	1%	3000	50.00
G	E	557	1	0	NC	NO	0%	YES	0%	NO	0%	0%	LC	-15%	over 45	61 to 80	0%	10.1 to 20	61 to 80	1%	over 45	61 to 100	0%	over 45	61 to 100	0%	1%	NO	YES	0.8	557	4000	-600	3400	0	1%	3000	50.00

Inputs and Calculation Notes:

Flow = $F = 220C\sqrt{A}$

- where:
- F = the required fire flow in litres per minute (rounded to the nearest 1000 Lpm)
 - C = coefficient related to the type of construction
 - = 1.5 for wood frame construction (structure essentially all combustible)
 - = 1.0 for ordinary construction (brick or other masonry walls, combustible floor and interior)
 - = 0.8 for non-combustible construction (unprotected metal structural components, masonry or metal walls)
 - = 0.6 for fire-resistive construction (fully protected frame, floors, roof)
 - A = the total floor area in square meters (including all storeys, but excluding basements at least 50% below grade) in the building being considered

Construction Classes

- WF = Wood frame construction
- OC = Ordinary construction
- NC = Non-combustible construction
- FC = Fire-resistive construction

Contents Factors

- NC = Non-combustible (-25%)
- LC = Limited combustible (-15%)
- C = Combustible (No charge)
- FB = Free burning (+15%)
- RB = Rapid burning (+25%)

Notes




Adequate Firewall with rating of not less than 2 hours is present between A1 and A2.
 All buildings are assumed non combustible with protected vertical openings as per FUS 2020 (i.e. min 1 hr rating of enclosures and openings with automatic closing doors, etc.).
 The architect will review and confirm the assumptions made regarding construction class, sprinkler systems, contents factor, minimum fire ratings, etc.

Footnotes

- ¹ Includes all storeys, but excluding basements at least 50% below grade in the building being considered
- ² Length x Height of Facing Wall of Exposure Building determined by multiplying the length of the facing wall of the exposure in feet by the height of the exposure in stories
- ³ Maximum exposure charge = 75%
- ⁴ Round to nearest 1,000 L/min

APPENDIX C


Drawings



#	DATE	DESCRIPTION
1	04/14/23	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA




KWA SITE DEVELOPMENT
 2453 Ashland Drive
 Burlington, ON L7L 7A9



SURVEY AND BENCHMARK NOTE
 EXISTING TOPOGRAPHIC INFORMATIONS SHOWN ON THE PLAN ARE BASED ON L.D. BARNES LTD. DRAWING (REF. NO. 25-25-300-00), DATED AUGUST 20, 2020.
 ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.


LEGEND	
× 100.00	PROPOSED ELEVATION
× 100.00 (SW)	PROPOSED SWALE ELEVATION
× (100.00)	PROPOSED PROPERTY LINE ELEVATION
× 100.00 (TC)	TOP OF CURB ELEVATION
× 100.00 (TW)	TOP OF WALL ELEVATION
× 100.00 (BW)	BOTTOM OF WALL ELEVATION
× 100.00 (G)	BOTTOM OF GUTTER ELEVATION
× 100.00 (TDC)	PROPOSED EDGE OF GUTTER ELEVATION
× 100.00 (EX)	PROPOSED TOP OF DEPRESSED CURB ELEVATION
—	EXISTING ELEVATION
○	PROPOSED CATCHBASIN
○	MAXIMUM 3:1 SLOPE (UNLESS OTHERWISE NOTE)
○	PROPOSED STORM MANHOLE
○	PROPOSED CATCHBASIN MANHOLE
○	PROPOSED DOUBLE CATCHBASIN
○	PROPOSED DOUBLE CATCHBASIN MANHOLE
○	PROPOSED SANITARY MANHOLE
○	PROPOSED VALVE AND BOX
○	PROPOSED HYDRANT
○	EXISTING CONTOUR
○	PROPOSED BOTTOM OF SWALE
○	EMERGENCY OVERLAND FLOW ROUTE
○	PROPERTY LINE
○	PROPOSED RETAINING WALL AS PER LANDSCAPE DESIGNS AND DETAILS
○	PROPOSED TRANSFORMER
○	EXISTING STORM MANHOLE
○	EXISTING CATCH BASIN



SITE GRADING PLAN
FIELDGATE COMMERCIAL
TAUNTON RD/BURKHOLDER DR.
 OPA 2025-001P - A 0825 - PRE 023-026/22
 PICKERING, ONTARIO
 PROJECT NO. 23810 DRAWN BY: BS CHECKED BY: BJ

SGP

TAUNTON ROAD



CROSSING TABLE

300 STM INV=171.62 200 SAN OBV=171.28 VERTICAL SEP=0.34m	300 STM INV=168.02 525 STM OBV=167.665 525 STM OUTER OBV=167.785 VERTICAL SEP=0.255m
300 STM INV=170.22 200 SAN OBV=169.88 VERTICAL SEP=0.34m	300 STM INV=167.21 200 SAN OBV=166.85 VERTICAL SEP=0.36m
300 STM INV=170.09 200 SAN OBV=169.78 VERTICAL SEP=0.31m	300 STM INV=166.49 525 STM OBV=166.305 525 STM OUTER OBV=166.405 VERTICAL SEP=0.085m
300 STM INV=168.62 200 SAN OBV=168.32 VERTICAL SEP=0.30m	300 STM INV=165.76 200 SAN OBV=165.36 VERTICAL SEP=0.40m
200 SAN INV=168.38 300 STM OBV=167.97 VERTICAL SEP=0.41m	200 SAN INV=166.31 300 STM OBV=165.17 VERTICAL SEP=1.14m
300 STM INV=169.21 200 SAN OBV=168.80 VERTICAL SEP=0.41m	250 STM INV=165.80 300 STM OBV=165.14 VERTICAL SEP=0.66m
300 STM INV=168.64 200 SAN OBV=167.50 VERTICAL SEP=1.14m	250 STM INV=165.83 200 SAN OBV=164.36 VERTICAL SEP=1.47m
300 STM INV=168.04 EX 200 SAN OBV=161.02 VERTICAL SEP=3.02m	

FUTURE RESIDENTIAL DEVELOPMENT AREA

LEGEND


- PROPOSED STORM SEWER (± 7500)
- PROPOSED STORM SEWER (≥ 7500)
- PROPOSED STORM MANHOLE (OPSD 701.010 - 701.012) (SIZE AS SHOWN)
- PROPOSED DOUBLE CATCHBASIN MANHOLE (OPSD 701.010) (SIZE AS SHOWN)
- PROPOSED STORM CATCHBASIN MANHOLE (OPSD 701.011 / 703.021) (SIZE AS SHOWN)
- PROPOSED CATCHBASIN (OPSD 705.010)
- PROPOSED DOUBLE CATCHBASIN (OPSD 705.020)
- EXISTING STORM SEWER
- EXISTING STORM MANHOLE
- EXISTING STORM CATCHBASIN MANHOLE
- EXISTING CATCHBASIN
- PROPOSED SANITARY SEWER
- PROPOSED SANITARY MANHOLE (OPSD 701.010) (SIZE AS SHOWN)
- EXISTING SANITARY SEWER
- EXISTING SANITARY MANHOLE
- PROPOSED WATERMAIN
- PROPOSED HYDRANT AND VALVE
- PROPOSED VALVE AND BOX
- EXISTING WATERMAIN
- EXISTING HYDRANT
- EXISTING VALVE AND BOX
- PROPOSED SUBDRIN BENEATH SWALE AS PER DETAILS ON SDP-2
- PROPOSED SWALE BOTTOM
- PIPE CROSSING

REVISION BLOCK


#	DATE	DESCRIPTION
1	04/14/23	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA



KWA
KWA SITE DEVELOPMENT
2455 Appleton Drive
Burlington, ON L7R 7A9




SURVEY AND BENCHMARK NOTE
EXISTING TOPOGRAPHIC INFORMATIONS SHOWN ON THIS PLAN ARE BASED ON L.D. BARNES LTD. DRAWING (REF. NO. 25-25-300-00), DATED AUGUST 20, 2020.
ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.



SITE SERVICING PLAN
FIELDGATE COMMERCIAL
TAUNTON RD/BURKHOLDER DR.
PICKERING, ONTARIO
PROJECT NO. 23810 | DRAWN BY: BS | CHECKED BY: BJ

SSP

TAUNTON ROAD WEST



- EROSION & SEDIMENT CONTROL NOTES**
- ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED PRIOR TO THE COMMENCEMENT OF WORK, MAINTAINED THROUGHOUT CONSTRUCTION, AND ONLY REMOVED UPON STABILIZATION OF THE DISTURBED AREAS.
 - SEDIMENT CONTROLS SHOULD BE INSPECTED ON A REGULAR BASIS WITH A MINIMUM FREQUENCY OF:
 - ON A WEEKLY BASIS
 - BEFORE AND AFTER EVERY RAINFALL EVENT (>12mm)
 - AFTER SIGNIFICANT SNOWMELT EVENTS
 - MONTHLY DURING INACTIVE PERIODS (> 30 DAYS)
 - DAILY DURING EXTENDED RAIN OR SNOWMELT PERIODS
 - REPAIRS TO ESC MEASURES MUST BE COMPLETED IN A TIMELY MANNER TO PREVENT SEDIMENT MIGRATION.
 - ADDITIONAL MATERIALS SUCH AS CLEAR STONE (12mm OR GREATER), FILTER FABRIC, PUMPS, HOSES AND SILTSOCKS TO BE KEPT ON-SITE AT ALL TIMES FOR CONDUCTING REPAIRS TO SEDIMENT CONTROL MEASURES.
 - ALL DISTURBED AREAS THAT WILL BE LEFT INACTIVE FOR MORE THAN THIRTY (30) DAYS ARE TO BE STABILIZED WITH THE EXCEPTION OF THE PREGRADED AREAS WHERE DRAINAGE IS COLLECTED IN AN APPROPRIATE EROSION CONTROL SYSTEM (E. POND, SEDIMENT BASIN).
 - ENGINEERED CHANGES TO THE ESC MEASURES MAY BE NEEDED AS SITE CONDITIONS CHANGE THROUGHOUT THE CONSTRUCTION PROCESS. THESE UPDATES MUST REFLECT BEST MANAGEMENT PRACTICES TO CONTROL SEDIMENT CONTROL AND EROSION ON-SITE AND SHOULD BE COMPLETED BASED ON DIRECTION FROM THE SITE ENGINEER. ADDITIONAL MEASURES MAY BE REQUIRED AS DIRECTED BY AN ENGINEER THROUGHOUT THE CONSTRUCTION PROCESS.
 - REFUELING IS TO TAKE PLACE ONLY WITHIN DESIGNATED AREAS AND SHALL BE A MINIMUM OF THIRTY METRES FROM ANY WATERCOURSE OR ENVIRONMENTALLY SENSITIVE AREA.
 - SILT CLEANUP EQUIPMENT SUCH AS ABSORBENT MEDIA IS TO BE MAINTAINED ON-SITE FOR IMMEDIATE USE IN THE EVENT OF A SPILL.
 - THE CONTRACTOR WILL BE RESPONSIBLE FOR CLEANUP AND RESTORATION, INCLUDING ALL COSTS, DUE TO THE RELEASE OF SEDIMENT FROM THE SITE.
 - THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS (EG. ROAD OCCUPANCY PERMIT, ACCESS PERMIT, ETC).
 - SPILLED OR TRACKED MATERIALS FROM THE CONTRACTOR'S HAULING VEHICLES ON ROADS WILL BE CLEANED UP AND THE SITE WILL BE LEFT IN A NEAT CONDITION AT THE END OF EACH WORKING DAY. THE CONTRACTOR WILL ARRANGE FOR OFF-SITE DISPOSAL OF ALL WASTE MATERIAL AND RUBBER TIRE TRACKS WITHIN A MAXIMUM OF 24 HOURS OF THE END OF EACH WORKING DAY.
 - SECONDARY CONTAMINANT IS REQUIRED FOR ALL STATIONARY NON-Self-Propelled PETROLEUM FILLED EQUIPMENT (E. PUMPS, GENERATORS, ETC.)
 - THE CONTRACTOR WILL KEEP THE SITE FREE FROM ACCUMULATIONS OF WASTE MATERIALS, SURPLUS FILL, TOPSOIL AND ALL DEBRIS SUCH AS BRICKS, BROKEN CEMENT OR UNSUITABLE FERTILIZER MATERIALS.
 - PROVIDE TERRAFIX SILT SACK (OR APPROVED EQUIVALENT) ON ANY EXISTING OR PROPOSED CATCH BASINS / CATCH-BASIN MANHOLES WITHIN THE INFLUENCE OF THE CONSTRUCTION REFER TO DETAIL ON SD.
 - SEDIMENT TO BE REMOVED FROM THE SEDIMENT BASINS BEFORE IT IS 25% FULL AND FROM SILT FENCE BEFORE IT IS 33% FULL.
 - SLOPE TRACKING TO BE USED AS NECESSARY WHERE EROSION ACTIVITIES ARE OBSERVED AND ON SLOPES IN EXCESS OF 3:1. SEE TRACKING DETAIL ON DWG SDP. MULCHING, SEEDING, OR EROSION BLANKETS MAY BE REQUIRED FOR FURTHER STABILIZATION.
 - ALL STOCKPILE AREAS LEFT EXPOSED FOR MORE THAN 30 DAYS SHALL BE STABILIZED WITH APPROPRIATE NON-INVASIVE SPECIES. WATER CONTINGENCY MEASURES SHALL BE IMPLEMENTED FOR EROSION CONTROL FOR APPROPRIATE STABILIZATION OF GROWING SEASON.
 - DUST CONTROL IS TO BE PROVIDED AS REQUIRED THROUGHOUT THE DURATION OF THE PROJECT TO PREVENT SIGNIFICANT DUST WITHIN THE AIR DURING CONSTRUCTION.
 - GOOD HOUSEKEEPING PRACTICES ARE TO BE FOLLOWED ON SITE DURING CONSTRUCTION AND MONITORED ON A DAILY BASIS. THIS INCLUDES, BUT IS NOT LIMITED TO:
 - APPROPRIATE STORAGE AND DISPOSAL OF CONSTRUCTION MATERIALS.
 - APPROPRIATE STORAGE AND DISPOSAL OF GARBAGE AND DEBRIS.
 - APPROPRIATE DISPOSAL OF CONCRETE WASTE TO AN APPROVED DISPOSAL FACILITY, AND
 - SECONDARY CONTAMINANT OF PETROLEUM-BASED PRODUCTS (E. OIL, ETC.).
- CITY OF PICKERING - EROSION AND SEDIMENT CONTROL GENERAL NOTES**
- PRIOR TO COMMENCEMENT OF ANY ON-SITE WORK/TOPSOIL STRIPPING, EROSION AND SEDIMENT CONTROL (ESC) MEASURES, AS PER APPROVED EROSION & SEDIMENT CONTROL PLAN, MUST BE INSTALLED TO PREVENT SURFACE RUNOFF FROM LEAVING THE SITE UNTREATED. ALL ESC MEASURES ARE TO BE MAINTAINED DURING THE PROJECT.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION, MAINTENANCE AND REMOVAL OF ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION, AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING.
 - SEDIMENT CONTROL FENCE TO USE GEOTEXTILE WITH WEAVE DENSITY OF 270R TERRAFIX OR EQUIVALENT.
 - ALL EXPOSED SOIL SHALL BE IMMEDIATELY STABILIZED AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING.
 - CHECK DAMS ARE TO BE USED IN ANY TEMPORARY DRAINAGE SWALES REQUIRED DURING CONSTRUCTION PERIOD.
 - ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED AND SHALL BE DETERMINED BY THE ENGINEER OR CITY OF PICKERING.
 - ALL SWALES ARE TO BE STABILIZED PRIOR TO USE.
 - INSPECTION OF THE PROPOSED EROSION AND SEDIMENT CONTROL MEASURES WILL OCCUR ON A WEEKLY BASIS. AFTER RAINFALL EVENTS EXCEEDING 10mm OR AFTER RAPID SNOW MELT EVENTS AND DAILY DURING EXTENDED RAIN OR SNOW MELT PERIODS. THE SILT CONTROL FENCE MUST BE INSPECTED FOR RIPS OR TEARS, BROKEN STAKES, BLOW OUTS AND ACCUMULATION OF SEDIMENT. THE SILT CONTROL FENCE MUST BE REPAIRED OR DAMAGED MATERIALS ACCUMULATED SEDIMENT MUST BE REMOVED FROM THE SILT CONTROL FENCE. WHEN ACCUMULATION REACHES 50% OF THE HEIGHT OF THE FENCE.
 - ROCK CHECK DAMS ARE TO BE CLEANED OF ALL ACCUMULATED SEDIMENT AS SOON AS SEDIMENT HAS ACCUMULATED TO A DEPTH GREATER THAN 50% OF ALL THE UPSTREAM CHECK DAMS.
 - CLEANING AND REPAIR OF MUD MATS AND ANY OTHER TEMPORARY SEDIMENT CONTROL MEASURES SHALL BE DONE AS NECESSARY THROUGH REGULAR INSPECTION OR AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING. ALL DAMAGED ESC MEASURES SHALL BE REPAIRED AND/OR REPLACED WITHIN 48 HOURS OF INSPECTION.
 - MATERIAL TO REPAIR DAMAGED ESC MEASURES MUST BE KEPT ON-SITE AT ALL TIMES.
 - THE ESC STRATEGIES ON THESE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRAD/ADAPTED AS SITE CONDITIONS CHANGE TO PREVENT SEDIMENT RELEASE. FAILED ESC MEASURES MUST BE REPAIRED IMMEDIATELY.
 - NO CONSTRUCTION ACTIVITY OR MACHINERY SHALL INTRUDE BEYOND THE SITE CONTROL FENCE OR LIMIT OF DEVELOPMENT. ALL CONSTRUCTION VEHICLES SHALL LEAVE THE SITE AT DESIGNATED LOCATIONS AS SHOWN ON THE PLAN. ALL MATERIALS AND EQUIPMENT SHALL BE STORED ON-SITE IN A DESIGNATED AREA. NO MATERIAL OR EQUIPMENT SHALL BE STORED ON THE MUNICIPAL ROAD OR IN ANY CONSTRUCTION VEHICLES WILL PARK ON MUNICIPAL ROADS.
 - SERVING OF CONSTRUCTION EQUIPMENT ON SITE IS PROHIBITED.
 - THE CONTRACTOR MUST CLEAN ADJACENT ROADS ON A REGULAR BASIS. THE ROAD SHALL BE, AT A MINIMUM SCRAPED DAILY AND FLUSHED (IF NECESSARY) ON FRIDAY EVENINGS OR SATURDAY MORNINGS.
 - DUST CONTROL TO BE PROVIDED BY WATER TRUCK OR CALCIUM CHLORIDE IS TO BE PROVIDED ON-SITE AND HAUL ROADWORKING AREAS ARE TO BE TREATED AS REQUIRED TO ENSURE THAT DUST IS CONTROLLED ON-SITE.
 - AT THE END OF CONSTRUCTION PERIOD, ACCUMULATED SEDIMENT IS TO BE REMOVED OFF-SITE PRIOR TO THE REMOVAL OF SILT FENCE.
 - ALL LITTER AND DEBRIS SHALL BE MONITORED AND DISPOSED OF DAILY OR AS NECESSARY THROUGH REGULAR INSPECTION.
 - ALL TOPSOIL STOCKPILES SHALL BE SURROUNDED WITH SEDIMENT CONTROL FENCE AND STABILIZED WITH SEED MIX AS PER THIS DRAWING.
 - DISTURBED AREAS ARE TO BE MINIMIZED TO THE EXTENT POSSIBLE AND STABILIZED AS THE WORK PROGRESSES. ANY AREA EXPOSED FOR MORE THAN 30 DAYS WILL BE STABILIZED.
- TRCA - STANDARD NOTES**
- EROSION AND SEDIMENT CONTROL (ESC) MEASURES WILL BE IMPLEMENTED PRIOR TO, AND MAINTAINED DURING THE CONSTRUCTION PHASES, TO PREVENT ENTRY OF SEDIMENT INTO THE WATER. ALL DAMAGED EROSION AND SEDIMENT CONTROL MEASURES SHOULD BE REPAIRED AND/OR REPLACED WITHIN 48 HOURS OF THE INSPECTION.
 - DISTURBED AREAS WILL BE MINIMIZED TO THE EXTENT POSSIBLE. ANY AREAS LEFT UNDISTURBED FOR A PERIOD LONGER THAN 30 DAYS TO BE TEMPORARILY OR PERMANENTLY STABILIZED AND RESTORED AS THE WORK PROGRESSES. UTILIZING TERRACEWAYS.
 - ALL WATERWAYS AND NEAR WATER WORKS WILL BE CONDUCTED IN ACCORD WITH APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES.
 - THE EROSION AND SEDIMENT CONTROL STRATEGIES OUTLINED ON THE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRAD/ADAPTED AS SITE CONDITIONS CHANGE TO MINIMIZE SEDIMENT LAIDEN RUNOFF FROM LEAVING THE WORK AREAS. AS THE PRESCRIBED MEASURES ON THE PLANS ARE NOT EFFECTIVE IN PREVENTING THE RELEASE OF SEDIMENT, THEN ALTERNATIVE MEASURES MUST BE IMPLEMENTED IMMEDIATELY TO MINIMIZE POTENTIAL ECOLOGICAL IMPACTS. TRCA ENFORCEMENT OFFICER SHOULD BE IMMEDIATELY CONTACTED. ADDITIONAL ESC MEASURES TO BE KEPT ON-SITE AS NECESSARY.
 - AN ENVIRONMENTAL MONITOR WILL ATTEND THE SITE TO INSPECT ALL NEW CONTROLS, AS WELL AS ON A REGULAR BASIS, OR FOLLOWING RAINFALL EVENTS. TO MONITOR ALL WORKS RELATED TO EROSION AND SEDIMENT CONTROL, DEWATERING OR UNWATERING RESTORATION AND IN-OR NEAR-WATERWORKS. SHOULD CONCERNS ARISE ON THE SITE, THE ENVIRONMENTAL MONITOR WILL CONTACT THE TRCA ENFORCEMENT OFFICER AS WELL AS THE PROPONENT.
 - ALL ACTIVITIES INCLUDING MAINTENANCE PROCEDURES, WILL BE CONTROLLED TO PREVENT THE ENTRY OF PETROLEUM PRODUCTS, DEBRIS, RUBBLE, CONCRETE OR OTHER DELETERIOUS SUBSTANCES INTO THE WATER. VEHICULAR REFUELING WILL BE CONDUCTED AT A MINIMUM OF 30 METERS FROM WATER.
 - THE PROPONENT CONTRACTOR SHALL MONITOR THE WEATHER SEVERAL DAYS IN ADVANCE OF THE ONSET OF THE PROJECT TO ENSURE THAT THE WORKS WILL BE CONDUCTED DURING FAVORABLE WEATHER CONDITIONS. THE CONTRACTOR WILL REMOVE ALL UNFIXED ITEMS FROM THE REGIONAL STORM FLOOD PLAN THE WORLD HAVE THE POTENTIAL TO CAUSE A SPILL OR AS OBSTRUCTION TO FLOW (E.G. FUEL TANKS, PORTA-POTTIES, MACHINERY, EQUIPMENT, CONSTRUCTION MATERIALS, ETC).
 - ALL DEWATERING/WATERING SHALL BE CONTROLLED AND RELEASED TO THE ENVIRONMENT AT LEAST 30 METERS FROM A WATERCOURSE OR WETLAND AND ALLOWED TO DRAIN THROUGH A WELL VEGETATED AREA. DEWATERING EFFLUENT SHALL BE SENT DIRECTLY TO AN APPROVED WATERWAY, WETLAND OR FOREST, OR ALLOWED TO DRAIN TO SOILS WITHIN THE WORK AREA. THESE CONTROL MEASURES SHALL BE MONITORED FOR THE EFFECTIVENESS AND MAINTAINED OR REVISED TO MEET THE OBJECTIVE OF PREVENTING THE RELEASE OF SEDIMENT LAIDEN WATER.
 - IN ORDER TO COMPLY WITH THE MIGRATORY BIRDS CONVENTION ACT, TRCA RECOMMENDS THAT REPAIRS BE COMPLETED BETWEEN AUGUST 1 AND APRIL 1.
 - PLEASE NOTIFY TRCA ENFORCEMENT OFFICER AND CONVICTION ACT MANAGER 4 HOURS PRIOR TO COMMENCING CONSTRUCTION.
 - AN ENVIRONMENTAL MONITOR WILL BE ON SITE AND PROVIDE ADVICE, TO ENSURE THAT ACTIVITIES THAT SHOULD HAVE A NEGATIVE IMPACT TO THE NATURAL ENVIRONMENT ARE EFFECTIVELY MITIGATED AS CONSTRUCTION PROCEEDS. THE ENVIRONMENTAL MONITOR SHALL NOTIFY THE TRCA ENFORCEMENT OFFICER AND PROJECT MANAGER IF AN ISSUE ARISE.
- SEQUENCE OF MAJOR CONSTRUCTION ACTIVITIES**
- INSTALL SILT FENCE AROUND THE SITE PERIMETER AS SHOWN ON THIS PLAN PER CITY OF PICKERING STANDARD DETAIL P-823.1 AS WELL AS THE SEDIMENT PROTECTION MEASURES AS SHOWN ON THIS PLAN.
 - INSTALL TEMPORARY CONSTRUCTION MUDMAT AT NORTHWEST CORNER OF GRADES PER DETAIL ON SDP.
 - BUILD TEMPORARY BERM ALONG EAST SIDE OF THE SITE TO PROPOSED GRADES AS SHOWN ON THIS PLAN.
 - BUILD 1m WIDE FLAT BOTTOM CUT-OFF SWALES WITH ROCK CHECK DAMS AT PROPOSED GRADES SHOWN ON THIS PLAN.
 - PLACE APPROVED FILL AND COMPACT BUILDING PAD TO SUBGRADE ELEVATIONS SHOWN ON THIS PLAN. CONFIRM FULLY TESTED CERTIFICATION OF BUILDING BY GEOTECHNICAL ENGINEER OF RECORD.
 - COMPLETE AS-BUILT SURVEY WORK.
- PERMIT CONDITIONS**
- ALL PERMIT HOLDERS SHALL:
 - NOTIFY THE DIRECTOR, OR HIS/HER DESIGNATE A MINIMUM OF TWO BUSINESS DAYS PRIOR TO THE COMMENCEMENT OR RECOMMENCEMENT OF ANY LAND DISTURBING ACTIVITY.
 - OBTAIN PERMISSION IN WRITING FROM THE DIRECTOR OR HIS/HER DESIGNATE PRIOR TO MODIFYING ANY ELEMENT OF THE EROSION AND SEDIMENT CONTROL PLAN.
 - INSTALL ALL CONTROL MEASURES AS IDENTIFIED IN THE APPROVED EROSION AND SEDIMENT CONTROL PLAN.
 - MAINTAIN ALL ROAD DRAINAGE SYSTEMS, STORMWATER DRAINAGE SYSTEMS, CONTROL AND IN-OR NEAR-WATERWORKS AND OTHER FACILITIES IDENTIFIED IN THE EROSION AND SEDIMENT CONTROL PLAN.
 - PROMPTLY REPAIR ANY SILTATION OR EROSION DAMAGE TO ADJACENT SURFACES AND DRAINAGE SYSTEMS RESULTING FROM LAND DEVELOPMENT OR DISTURBING ACTIVITIES.
 - INSPECT THE SEDIMENTATION CONTROL MEASURES AT LEAST ONCE PER WEEK AND AFTER EACH RAINFALL OF AT LEAST ONE CENTIMETER AND MAKE NEEDED REPAIRS.
 - ALLOW CITY OFFICERS OR AGENTS OF THE CITY TO ENTER THE SITE FOR THE PURPOSE OF INSPECTING FOR COMPLIANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN AND PERFORMING ANY WORK NECESSARY TO BRING THE SITE INTO COMPLIANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN.
 - MAINTAIN A COPY OF THE PERMIT ON THE SITE.
 - NOTIFY ALL SUB-CONTRACTORS AND SUPPLIERS OF APPROVED ACCESS ROUTES TO THE SITE AND ENSURE COMPLIANCE WITH THESE INSTRUCTIONS.
 - MAINTAIN ALL ROADS IN THE SAME OR BETTER CONDITION THAN EXISTED PRIOR TO THE COMMENCEMENT OF THE WORK AND KEEP ALL ROADS FREE FROM ANY MATERIALS OR EQUIPMENT FROM THE WORK SET OUT IN THE PERMIT AND
 - ENSURE THAT NO CONSTRUCTION MACHINERY IS OPERATED IN CONTRAVENANCE OF BY-LAW NUMBER 3821, AS AMENDED, (NOISE BY-LAW) OR ANY SUCCESSOR THERETO.
 - THE CITY:
 - UPON THE FAILURE BY THE PERMIT HOLDER TO COMPLETE ALL OR PART OF THE WORKS IN THE TIME SPECIFIED IN THE EROSION AND SEDIMENT CONTROL PLAN, THE CITY MAY DRAW THE APPROPRIATE AMOUNT FROM THE SECURITIES POSTED AND USE THE FUNDS TO ARRANGE FOR THE COMPLETION OF THE SAID WORKS OR ANY PART THEREOF.
 - UPON FAILURE BY THE PERMIT HOLDER TO INSTALL, REPAIR OR MAINTAIN A SPECIFIC PART OF THE WORKS AS REQUESTED BY THE CITY, AND IN THE TIME REQUESTED, THE CITY MAY AT ANY TIME AUTHORIZE THE USE OF ALL OR PART OF THE SECURITIES TO PAY THE COST OF ANY PART OF THE WORKS IF MAY IN ITS OR THEIR ABSOLUTE DISCRETION DEEM NECESSARY; AND
 - IN THE CASE OF EMERGENCY REPAIRS OR CLEANUP, THE CITY MAY UNDERTAKE ANY NECESSARY WORKS AT THE EXPENSE OF THE PERMIT HOLDER AND REIMBURSE ITSELF OUT OF SECURITIES POSTED BY THE APPLICANT.

LEGEND

- SLT -SLT- PROPOSED SILT FENCE
- 184.05- PROPOSED CONTOUR
- 184.05- EXISTING CONTOUR
- ROCK CHECK DAM
- PROPOSED INTERCEPTOR SWALE AND FLOW DIRECTION AS PER (OPSD 219.211)
- EXISTING SWALE TO REMAIN
- CONSTRUCTION ENTRANCE AS PER REGION OF DURHAM STANDARD S-301.050
- SILTSACK INLET SEDIMENT CONTROL DEVICE
- EXISTING STORM SEWER
- EXISTING STORM MANHOLE
- EXISTING CATCH BASIN
- LIMIT OF REGRADING
- SWALE TRIBUTARY BOUNDARY

24 HOUR CONTACTS:
DAN MARCO TAVANELLO 416-889-8104
BRUNO TILLEY 416-777-8919

METRIC SCALE
0 5 10 20
1:500

PERMIT HOLDERS SHALL:

- NOTIFY THE DIRECTOR, OR HIS/HER DESIGNATE A MINIMUM OF TWO BUSINESS DAYS PRIOR TO THE COMMENCEMENT OR RECOMMENCEMENT OF ANY LAND DISTURBING ACTIVITY.
- OBTAIN PERMISSION IN WRITING FROM THE DIRECTOR OR HIS/HER DESIGNATE PRIOR TO MODIFYING ANY ELEMENT OF THE EROSION AND SEDIMENT CONTROL PLAN.
- INSTALL ALL CONTROL MEASURES AS IDENTIFIED IN THE APPROVED EROSION AND SEDIMENT CONTROL PLAN.
- MAINTAIN ALL ROAD DRAINAGE SYSTEMS, STORMWATER DRAINAGE SYSTEMS, CONTROL AND IN-OR NEAR-WATERWORKS AND OTHER FACILITIES IDENTIFIED IN THE EROSION AND SEDIMENT CONTROL PLAN.
- PROMPTLY REPAIR ANY SILTATION OR EROSION DAMAGE TO ADJACENT SURFACES AND DRAINAGE SYSTEMS RESULTING FROM LAND DEVELOPMENT OR DISTURBING ACTIVITIES.
- INSPECT THE SEDIMENTATION CONTROL MEASURES AT LEAST ONCE PER WEEK AND AFTER EACH RAINFALL OF AT LEAST ONE CENTIMETER AND MAKE NEEDED REPAIRS.
- ALLOW CITY OFFICERS OR AGENTS OF THE CITY TO ENTER THE SITE FOR THE PURPOSE OF INSPECTING FOR COMPLIANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN AND PERFORMING ANY WORK NECESSARY TO BRING THE SITE INTO COMPLIANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN.
- MAINTAIN A COPY OF THE PERMIT ON THE SITE.
- NOTIFY ALL SUB-CONTRACTORS AND SUPPLIERS OF APPROVED ACCESS ROUTES TO THE SITE AND ENSURE COMPLIANCE WITH THESE INSTRUCTIONS.
- MAINTAIN ALL ROADS IN THE SAME OR BETTER CONDITION THAN EXISTED PRIOR TO THE COMMENCEMENT OF THE WORK AND KEEP ALL ROADS FREE FROM ANY MATERIALS OR EQUIPMENT FROM THE WORK SET OUT IN THE PERMIT AND
- ENSURE THAT NO CONSTRUCTION MACHINERY IS OPERATED IN CONTRAVENANCE OF BY-LAW NUMBER 3821, AS AMENDED, (NOISE BY-LAW) OR ANY SUCCESSOR THERETO.

THE CITY:

- UPON THE FAILURE BY THE PERMIT HOLDER TO COMPLETE ALL OR PART OF THE WORKS IN THE TIME SPECIFIED IN THE EROSION AND SEDIMENT CONTROL PLAN, THE CITY MAY DRAW THE APPROPRIATE AMOUNT FROM THE SECURITIES POSTED AND USE THE FUNDS TO ARRANGE FOR THE COMPLETION OF THE SAID WORKS OR ANY PART THEREOF.
- UPON FAILURE BY THE PERMIT HOLDER TO INSTALL, REPAIR OR MAINTAIN A SPECIFIC PART OF THE WORKS AS REQUESTED BY THE CITY, AND IN THE TIME REQUESTED, THE CITY MAY AT ANY TIME AUTHORIZE THE USE OF ALL OR PART OF THE SECURITIES TO PAY THE COST OF ANY PART OF THE WORKS IF MAY IN ITS OR THEIR ABSOLUTE DISCRETION DEEM NECESSARY; AND
- IN THE CASE OF EMERGENCY REPAIRS OR CLEANUP, THE CITY MAY UNDERTAKE ANY NECESSARY WORKS AT THE EXPENSE OF THE PERMIT HOLDER AND REIMBURSE ITSELF OUT OF SECURITIES POSTED BY THE APPLICANT.

REVISION BLOCK

#	DATE	DESCRIPTION
1	04/14/25	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA

REGISTERED PROFESSIONAL ENGINEER
B. JACKSON
100210382
2012-4-2025
PROVINCE OF ONTARIO

KWA
KWA CONSULTANTS
1000 SHEPPARD AVENUE EAST
SUITE 100
SCARBOROUGH, ONTARIO M1S 1T7


NORTH ARROW

SURVEY AND BENCHMARK NOTE
EXISTING TOPOGRAPHIC INFORMATION SHOWN ON THIS PLAN ARE BASED ON J.D. BARNES LTD. DRAWING (REF. NO. 25-25-00-01, DATED AUGUST 20, 2020).
ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.

EROSION AND SEDIMENT CONTROL PLAN - 1
TAUNTON COMMERCIAL
TAUNTON RD/BURKHOLDER DR.
PICKERING, ONTARIO
CITY OF PICKERING FILE FB 01-2025
PROJECT NO. 23810
DRAWN BY: BS
CHECKED BY: BJ

ESC-1

TAUNTON ROAD WEST



- ### EROSION & SEDIMENT CONTROL NOTES
- ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED PRIOR TO THE COMMENCEMENT OF WORK, MAINTAINED THROUGHOUT CONSTRUCTION, AND ONLY REMOVED UPON STABILIZATION OF THE DISTURBED AREA.
 - SEDIMENT CONTROLS SHOULD BE INSPECTED ON A REGULAR BASIS WITH A MINIMUM FREQUENCY OF:
 - ON A WEEKLY BASIS
 - BEFORE AND AFTER EVERY RAINFALL EVENT (>12mm)
 - AFTER SIGNIFICANT SNOWMELT EVENTS
 - MONTHLY DURING INACTIVE PERIODS (> 30 DAYS)
 - DAILY DURING EXTENDED RAIN OR SNOWMELT PERIODS
 - REPAIRS TO ESC MEASURES MUST BE COMPLETED IN A TIMELY MANNER TO PREVENT SEDIMENT MIGRATION.
 - ADDITIONAL MATERIALS SUCH AS CLEAR STONE (12mm OR GREATER), FILTER FABRIC, PUMPS, HOSES AND SILTBOX TO BE KEPT ON-SITE AT ALL TIMES FOR CONDUCTING REPAIRS TO SEDIMENT CONTROL.
 - ALL DISTURBED AREAS THAT WILL BE LEFT INACTIVE FOR MORE THAN THIRTY (30) DAYS ARE TO BE STABILIZED WITH THE EXCEPTION OF THE PREGRADED AREAS WHERE DAMAGE IS COLLECTED IN AN APPROPRIATE EROSION CONTROL SYSTEM (E. POND, SEDIMENT BASIN).
 - ENGINEERED CHANGES TO THE ESC MEASURES MAY BE NEEDED AS SITE CONDITIONS CHANGE THROUGHOUT THE CONSTRUCTION PROCESS. THESE UPDATES MUST REFLECT BEST MANAGEMENT PRACTICES TO CONTROL SEDIMENT CONTROL AND EROSION CONTROL AND SHOULD BE COMPLETED BASED ON DIRECTION FROM THE SITE ENGINEER. ADDITIONAL MEASURES MAY BE REQUIRED AS DIRECTED BY AN ENGINEER THROUGHOUT THE CONSTRUCTION PROCESS.
 - REFUELING IS TO TAKE PLACE ONLY WITH DESIGNATED AREAS AND SHALL BE A MINIMUM OF THIRTY METRES FROM ANY WATERCOURSE OR ENVIRONMENTALLY SENSITIVE AREA.
 - SILT CLEANUP EQUIPMENT SUCH AS ABSORBENT MEDIA IS TO BE MAINTAINED ON-SITE FOR IMMEDIATE USE IN THE EVENT OF A SPILL.
 - THE CONTRACTOR WILL BE RESPONSIBLE FOR CLEAN-UP AND RESTORATION, INCLUDING ALL COSTS, DUE TO THE RELEASE OF SEDIMENT FROM THE SITE.
 - THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS (E.G. ROAD OCCUPANCY PERMIT, ACCESS PERMIT, ETC).
 - SPILLED OR TRACKED MATERIALS FROM THE CONTRACTOR'S HAULING VEHICLES ON ROADS WILL BE CLEANED UP AND THE SITE WILL BE LEFT IN A NEAT CONDITION AT THE END OF EACH WORKING DAY. THE CONTRACTOR WILL ARRANGE FOR OFF-SITE DISPOSAL OF ALL WASTE MATERIAL AND RUBBISH IN A MANNER THAT COMPLIES WITH ALL LAWS AND REGULATIONS.
 - SECONDARY CONTAINMENT IS REQUIRED FOR ALL STATIONARY NON-Self-PROPELLED PETROLEUM FILLED EQUIPMENT (E. PUMPS, GENERATORS, ETC).
 - THE CONTRACTOR WILL KEEP THE SITE FREE FROM ACCUMULATIONS OF WASTE MATERIALS, SURPLUS FILL, TOPSOIL, AND ALL DEBRIS SUCH AS BOULDERS, BROKEN ASPHALT, BROKEN CONCRETE OR UNSUITABLE EARTH MATERIALS.
 - PROVIDE TERRAFIX SILT SACK (OR APPROVED EQUIVALENT) ON ANY EXISTING OR PROPOSED CATCH BASIN / CATCHBASIN MANHOLES WITHIN THE INFLUENCE OF THE CONSTRUCTION AREA.
 - SEDIMENT TO BE REMOVED FROM THE SEDIMENT BASIN BEFORE IT IS 25% FULL AND FROM SILT FENCE BEFORE IT IS 33% FULL.
 - SLOPE TRACKING TO BE USED AS NEEDED WHERE EROSION ACTIVITIES ARE OBSERVED AND ON SLOPES IN EXCESS OF 3:1. SEE TRACKING DETAIL ON DWG SDP. MULCHING, SEEDING, OR EROSION BLANKETS MAY BE REQUIRED FOR FURTHER STABILIZATION.
 - ALL STOCKPILE AREAS LEFT EXPOSED FOR MORE THAN 30 DAYS SHALL BE STABILIZED WITH APPROPRIATE NON-INVASIVE SPECIES. WINTER CONTINGENCY MEASURES SHALL BE IMPLEMENTED AS EROSION CONTROL FOR APPROPRIATE STABILIZATION OUTSIDE THE GROWING SEASON.
 - DUST CONTROL IS TO BE PROVIDED AS REQUIRED THROUGHOUT THE DURATION OF THE PROJECT TO PREVENT SIGNIFICANT DUST WITHIN THE AIR DURING CONSTRUCTION.
 - GOOD HOUSEKEEPING PRACTICES ARE TO BE FOLLOWED ON-SITE DURING CONSTRUCTION AND MONITORED ON A DAILY BASIS. THIS INCLUDES, BUT IS NOT LIMITED TO:
 - APPROPRIATE STORAGE AND DISPOSAL OF CONSTRUCTION MATERIALS.
 - APPROPRIATE STORAGE AND DISPOSAL OF DEBRIS AND EQUIPMENT SHALL BE STORED ON-SITE IN A DESIGNATED AREA. NO MATERIAL OR EQUIPMENT SHALL BE STORED ON THE MUNICIPAL RIGHT OF WAY. NO CONSTRUCTION VEHICLES WILL PARK ON MUNICIPAL ROADS.
 - APPROPRIATE DISPOSAL OF CONCRETE WASTE TO AN APPROVED DISPOSAL FACILITY, AND
 - SECONDARY CONTAINMENT OF PETROLEUM BASED PRODUCTS (GERRY CANS, OIL, ETC.).

- ### CITY OF PICKERING - EROSION AND SEDIMENT CONTROL GENERAL NOTES
- PRIOR TO COMMENCEMENT OF ANY ON-SITE WORK (TOPSOIL STRIPPING, EROSION AND SEDIMENT CONTROL (ESC) MEASURES, AS PER APPROVED EROSION & SEDIMENT CONTROL PLAN, MUST BE ESTABLISHED TO PREVENT SURFACE RUNOFF LEAVING THE SITE UNTIL THE ESC MEASURES ARE TO BE MAINTAINED UNTIL THE SITE HAS BEEN STABILIZED.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION, MAINTENANCE AND REMOVAL OF ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING.
 - SEDIMENT CONTROL FENCE TO USE GEOTEXTILE WITH WEAVE DENSITY OF 200 TERRAFIX OR EQUIVALENT.
 - ALL EXPOSED SOIL SHALL BE IMMEDIATELY STABILIZED AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING.
 - CHECK DAMS ARE TO BE USED IN ANY TEMPORARY DRAINAGE SWALES REQUIRED DURING CONSTRUCTION PERIOD.
 - ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES MAY BE REQUIRED AND SHALL BE DETERMINED BY THE ENGINEER OR CITY OF PICKERING.
 - ALL SWALES ARE TO BE STABILIZED PRIOR TO USE.
 - INSPECTION OF THE PROPOSED EROSION AND SEDIMENT CONTROL MEASURES WILL OCCUR ON A WEEKLY BASIS. AFTER RAINFALL EVENTS EXCEEDING 10mm OR AFTER RAPID SNOW MELT EVENTS AND DAILY DURING EXTENDED RAIN OR SNOW MELT PERIODS. THE SILT CONTROL FENCE MUST BE INSPECTED FOR RIPS OR TEARS, BROKEN STAKES, BLOW OUTS AND ACCUMULATION OF SEDIMENT. THE SILT CONTROL FENCE MUST BE REPAIRED AND RE-ACCUMULATED IMMEDIATELY WHEN DAMAGED. ACCUMULATED SEDIMENT MUST BE REMOVED FROM THE SILT CONTROL FENCE WHEN ACCUMULATION REACHES 50% OF THE HEIGHT OF THE FENCE.
 - ROCK CHECK DAMS ARE TO BE CLEANED OF ALL ACCUMULATED SEDIMENT AS SOON AS SEDIMENT HAS ACCUMULATED TO A DEPTH GREATER THAN 50% OF ALL THE UPSTREAM CHECK DAMS.
 - CLEANING AND REPAIR OF MUD MATS AND ANY OTHER TEMPORARY SEDIMENT CONTROL MEASURES SHALL BE DONE AS NECESSARY THROUGHOUT INSPECTION OR AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING. ALL DAMAGED ESC MEASURES SHALL BE REPAIRED AND/OR REPLACED WITHIN 48 HOURS OF INSPECTION.
 - MATERIALS TO REPAIR DAMAGED ESC MEASURES MUST BE KEPT ON-SITE AT ALL TIMES.
 - THE ESC STRATEGIES ON THESE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE CONDITIONS CHANGE TO PREVENT SEDIMENT RELEASES. FAILED ESC MEASURES MUST BE REPAIRED IMMEDIATELY.
 - NO CONSTRUCTION ACTIVITY OR MACHINERY SHALL INTRUDE BEYOND THE SITE CONTROL FENCE OR LIMIT OF DEVELOPMENT. ALL CONSTRUCTION VEHICLES SHALL LEAVE THE SITE AT DESIGNATED LOCATIONS AS SHOWN ON THE PLAN. ALL MATERIALS AND EQUIPMENT SHALL BE STORED IN A DESIGNATED AREA. NO MATERIAL OR EQUIPMENT SHALL BE STORED ON THE MUNICIPAL RIGHT OF WAY. NO CONSTRUCTION VEHICLES WILL PARK ON MUNICIPAL ROADS.
 - SERVICES OF CONSTRUCTION EQUIPMENT ON SITE IS PROHIBITED.
 - THE CONTRACTOR MUST CLEAN ADJACENT ROADS ON A REGULAR BASIS. THE ROAD SHALL BE, AT A MINIMUM SCRAPPED DAILY AND FLUSHED (IF NECESSARY) ON FRIDAY EVENINGS OR SATURDAY MORNINGS.
 - DUST CONTROL TO BE RECEIVED DAILY. WATER TRUCK OR CALCIUM CHLORIDE IS TO BE PROVIDED ON SITE AND HAUL ROADS WORKING AREAS ARE TO BE TREATED AS REQUIRED TO DUST DURING THE DAY THAT MUST BE CONTROLLED TO CAUSE A SPILL OR AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING.
 - AT THE END OF CONSTRUCTION PERIOD, ACCUMULATED SEDIMENT IS TO BE REMOVED OFF-SITE PRIOR TO THE REMOVAL OF SILT FENCE.
 - ALL LITTER AND DEBRIS SHALL BE MONITORED AND DISPOSED OF DAILY OR AS NECESSARY THROUGHOUT CONSTRUCTION.
 - ALL TOPSOIL STOCKPILES SHALL BE SURROUNDED WITH SEDIMENT CONTROL FENCE AND STABILIZED WITH SEED MIX AS PER THIS DRAWING.
 - DISTURBED AREAS ARE TO BE MINIMIZED TO THE EXTENT POSSIBLE AND STABILIZED AS THE WORK PROGRESSES. ANY AREA EXPOSED FOR MORE THAN 30 DAYS WILL BE STABILIZED.

- ### TRCA - STANDARD NOTES
- EROSION AND SEDIMENT CONTROL (ESC) MEASURES WILL BE IMPLEMENTED PRIOR TO, AND MAINTAINED DURING THE CONSTRUCTION PHASES. TO PREVENT ENTRY OF SEDIMENT INTO THE WATER, ALL DAMAGED EROSION AND SEDIMENT CONTROL MEASURES SHOULD BE REPAIRED AND/OR REPLACED WITHIN 48 HOURS OF THE INSPECTION.
 - DISTURBED AREAS WILL BE MINIMIZED TO THE EXTENT POSSIBLE. ANY AREAS LEFT UNDISTURBED FOR A PERIOD LONGER THAN 30 DAYS TO BE TEMPORARILY OR PERMANENTLY STABILIZED AND RESTORED AS THE WORK PROGRESSES. UTILIZING TERRACEING.
 - IN WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN DRY WITH APPROPRIATE EROSION AND SEDIMENT CONTROLS.
 - THE EROSION AND SEDIMENT CONTROL STRATEGIES OUTLINED ON THE PLANS ARE NOT STATIC AND MAY NEED TO BE UPGRADED/AMENDED AS SITE CONDITIONS CHANGE TO MINIMIZE SEDIMENT LACED RUNOFF FROM LEAVING THE WORK AREAS. IF THE PRESCRIBED MEASURES ON THE PLANS ARE NOT EFFECTIVE IN PREVENTING THE RELEASE OF A DELETERIOUS SUBSTANCE, INCLUDING SEDIMENT, THEN ALTERNATIVE MEASURES MUST BE IMPLEMENTED IMMEDIATELY TO MINIMIZE THE POTENTIAL ECOTOLOGICAL IMPACTS. TRCA ENFORCEMENT OFFICER SHOULD BE IMMEDIATELY CONTACTED. ADDITIONAL ESC MEASURES TO BE KEPT ON-SITE AND USED AS NECESSARY.
 - AN ENVIRONMENTAL MONITOR WILL ATTEND THE SITE TO INSPECT ALL NEW CONTROLS, AS WELL AS ON A REGULAR BASIS, OR FOLLOWING RAINFALL/SNOWMELT EVENT, TO MONITOR THE EROSION AND SEDIMENT CONTROL, SEDIMENTATION OR UNWANTED RESTORATION AND/OR NEAR-WATER WORKS. SHOULD CONCERNS ARISE ON THE SITE THE ENVIRONMENTAL MONITOR WILL CONTACT THE TRCA ENFORCEMENT OFFICER AS WELL AS THE PROPRIETOR.
 - ALL ACTIVITIES INCLUDING MAINTENANCE PROCEDURES WILL BE CONTROLLED TO PREVENT THE ENTRY OF PETROLEUM PRODUCTS, DEBRIS, RUBLE, CONCRETE OR OTHER HAZARDOUS MATERIALS INTO THE WATER. VEHICULAR REFUELING AND MAINTENANCE WILL BE CONDUCTED AT A MINIMUM OF 3 METERS FROM WATER.
 - THE PROPRIETOR/CITY SHALL MONITOR THE WEATHER SEVERAL DAYS IN ADVANCE OF THE ONSET OF THE PROJECT TO ENSURE THAT THE WORKS WILL BE CONDUCTED DURING FAVORABLE WEATHER CONDITIONS. SHOULD UNEXPECTED STORMS ARISE, THE CONTRACTOR WILL REMOVE ALL UNFIXED ITEMS FROM THE REGIONAL STORM FLOOD PLAN TO PREVENT THE POTENTIAL TO CAUSE A SPILL OR AS DIRECTED BY THE ENGINEER OR CITY OF PICKERING.
 - ALL DRAINAGE/WATERWAYS SHALL BE TREATED AND RELEASED TO THE ENVIRONMENT AT LEAST 30 METERS FROM A WATERCOURSE OR WETLAND AND ALLOWED TO DRAIN THROUGH A WELL VEGETATED AREA. NO SEWERAGE EFFLUENT SHALL BE SENT DIRECTLY TO ANY WATERCOURSE, WETLAND OR FOREST, OR ALLOWED TO DRAIN ONTO DISTURBED SOIL WITHIN THE WORK AREA. THESE CONTROL MEASURES SHALL BE MONITORED FOR THE EFFECTIVENESS AND MAINTAINED OR REPAIRED TO MEET THE OBJECTIVE OF PREVENTING THE RELEASE OF SEDIMENT AND WATER.
 - IN ORDER TO COMPLY WITH THE MORTGARY BIRDS CONVENTION ACT, TRCA RECOMMENDS THAT REMOVALS BE COMPLETED BETWEEN AUGUST 1 AND APRIL 1.
 - PLEASE NOTIFY TRCA ENFORCEMENT OFFICER AND TRCA PROJECT MANAGER 48 HOURS PRIOR TO COMMENCING CONSTRUCTION.
 - AN ENVIRONMENTAL MONITOR WILL BE ON-SITE AND PROVIDE ADVICE TO ENSURE THAT ACTIVITIES THAT SHOULD HAVE A NEGATIVE IMPACT TO THE NATURAL ENVIRONMENT ARE EFFECTIVELY MITIGATED AS CONSTRUCTION PROGRESSES. THE ENVIRONMENTAL MONITOR SHALL NOTIFY THE TRCA ENFORCEMENT OFFICER AND PROJECT MANAGER IF AN ISSUE ARISES.

LEGEND

- PROPOSED STORM SEWER (<7500)
- PROPOSED STORM SEWER (>=7500)
- PROPOSED DOUBLE MANHOLE
- PROPOSED DOUBLE CATCHBASIN MANHOLE
- PROPOSED STORM CATCHBASIN MANHOLE
- PROPOSED CATCHBASIN
- PROPOSED DOUBLE CATCHBASIN
- PROPOSED SILT FENCE
- PROPOSED CONTOUR
- EXISTING CONTOUR
- ROCK CHECK DAM
- PROPOSED INTERCEPTOR SWALE AND FLOW DIRECTION AS PER (OSPD 219.211)
- EXISTING SWALE TO REMAIN
- CONSTRUCTION ENTRANCE AS PER REGION OF DURHAM STANDARD S-301.050
- TERRAFIX SILT SACK INLET SEDIMENT CONTROL DEVICE
- EXISTING STORM SEWER
- EXISTING STORM MANHOLE
- EXISTING CATCH BASIN
- LIMIT OF REGRADING
- SWALE TRIBUTARY BOUNDARY

SEQUENCE OF MAJOR CONSTRUCTION ACTIVITIES



- INSTALL SILT FENCING AROUND THE SITE PERIMETER AS SHOWN ON THIS PLAN PER CITY OF PICKERING STANDARD DETAIL P-423.1 AS WELL AS THE SEDIMENT PROTECTION MEASURES AS SHOWN ON THIS PLAN.
- INSTALL TEMPORARY CONSTRUCTION MUDMAT AT NORTHWEST CORNER OF SITE AS PER DETAIL ON SDP.
- BUILD TEMPORARY BERM ALONG EAST SIDE OF THE SITE TO PROPOSED GRADES SHOWN ON THIS PLAN.
- BUILDING 1st WIDE FLAT BOTTOM CUT-OFF SWALES WITH ROCK CHECK DAMS AT PROPOSED GRADES SHOWN ON THIS PLAN.
- PLACE APPROVED FILL AND COMPACT FILL TO SUBGRADE ELEVATIONS SHOWN ON THIS PLAN. CONFIRM FULLY TESTED CERTIFICATION OF BUILDING BY GEOTECHNICAL ENGINEER OF RECORD.
- GRADE THE REST OF THE SITE AS SHOWN ON THIS PLAN AND MONITOR EROSION AND SEDIMENT TRAPS REGULARLY TO ENSURE THEIR FUNCTIONS ARE MAINTAINED.
- COMPLETE AS-BUILT SURVEY WORK.

PERMIT CONDITIONS

- ALL PERMIT HOLDERS SHALL:
 - NOTIFY THE DIRECTOR, OR HIS/HER DESIGNATE A MINIMUM OF TWO BUSINESS DAYS PRIOR TO THE COMMENCEMENT OR RECOMMENCEMENT OF ANY LAND DISTURBING ACTIVITY.
 - OBTAIN PERMISSION IN WRITING FROM THE DIRECTOR OR HIS/HER DESIGNATE PRIOR TO MODIFYING ANY ELEMENT OF THE EROSION AND SEDIMENT CONTROL PLAN.
 - INSTALL ALL CONTROL MEASURES AS IDENTIFIED IN THE APPROVED EROSION AND SEDIMENT CONTROL PLAN.
 - MAINTAIN ALL ROAD DRAINAGE SYSTEMS, STORMWATER DRAINAGE SYSTEMS, CONTROL MEASURES AND OTHER FACILITIES IDENTIFIED IN THE EROSION AND SEDIMENT CONTROL PLAN.
 - PROMPTLY REPAIR ANY SILLATION OR EROSION DAMAGE TO ADJACENT SURFACES AND DRAINAGEWAYS RESULTING FROM LAND DEVELOPING OR DISTURBING ACTIVITIES.
 - INSPECT THE SEDIMENTATION CONTROL MEASURES AT LEAST ONCE PER WEEK AND AFTER EACH RAINFALL OF AT LEAST ONE CENTIMETER AND MAKE NEEDED REPAIRS.
 - ALLOW CITY OFFICERS OR AGENTS OF THE CITY TO ENTER THE SITE FOR THE PURPOSE OF INSPECTING FOR COMPLIANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN OR PERFORMING ANY WORK NECESSARY TO BRING THE SITE INTO COMPLIANCE WITH THE EROSION AND SEDIMENT CONTROL PLAN.
 - MAINTAIN A COPY OF THE PERMIT ON THE SITE.
 - NOTIFY ALL SUB-CONTRACTORS AND SUPPLIERS OF APPROVED ACCESS ROUTES TO THE SITE AND ENSURE COMPLIANCE WITH THESE INSTRUCTIONS.
 - MAINTAIN ALL ROADS IN SAME OR BETTER CONDITION THAN EXISTED PRIOR TO THE COMMENCEMENT OF THE WORK AND KEEP ALL ROADS FREE FROM ANY MATERIALS OR EQUIPMENT FROM THE WORK SET OUT IN THE PERMIT.
 - ENSURE THAT NO CONSTRUCTION MACHINERY IS OPERATED IN CONTRAVENTION OF BY-LAW NUMBER 3821, AS AMENDED, (NOISE BY-LAW) OR ANY SUCCESSOR THEREOF.
- THE CITY:
 - UPON THE FAILURE BY THE PERMIT HOLDER TO COMPLETE ALL OR PART OF THE WORKS IN THE STIPULATED IN THE EROSION AND SEDIMENT CONTROL PLAN, THE CITY MAY DRAW THE APPROPRIATE AMOUNT FROM THE SECURITIES POSTED AND USE THE FUNDS TO ARRANGE FOR THE COMPLETION OF THE SAID WORKS, OR ANY PART THEREOF.
 - UPON FAILURE BY THE PERMIT HOLDER TO INSTALL, REPAIR OR MAINTAIN A SPECIFIC PART OF THE WORKS AS REQUESTED BY THE CITY, AND IN THE TIME REQUESTED, THE CITY MAY AT ANY TIME AUTHORIZE THE USE OF ITS OWN PARTS OR CONTRACTORS TO PAY THE COST OF ANY PART OF THE WORKS IT MAY IN ITS OR THEIR ABSOLUTE DISCRETION DEEM NECESSARY.
 - IN THE CASE OF EMERGENCY REPAIRS OR CLEANUP, THE CITY MAY UNDERTAKE THE NECESSARY WORKS AT THE EXPENSE OF THE PERMIT HOLDER AND REIMBURSE ITSELF OUT OF SECURITIES POSTED BY THE APPLICANT.


REVISION BLOCK

#	DATE	DESCRIPTION
1	04/14/23	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA



EXISTING TOPOGRAPHIC INFORMATION SHOWN ON THIS PLAN ARE BASED ON J.D. BARNES LTD. DRAWING (REF. NO. 25-25-00-00), DATED AUGUST 20, 2020.

ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.




EROSION AND SEDIMENT CONTROL PLAN - 2

FIELD CONTACT COMMERCIAL
TAUNTON RD/BURKHOLDER DR.
PICKERING, ONTARIO CITY OF PICKERING FILE FB 01-2025
PROJECT NO. 23810 DRAWN BY: BS CHECKED BY: BJ

ESC-2

TAUNTON ROAD WEST



GENERAL NOTES

- ALL WORK SHALL BE IN ACCORDANCE WITH THE CITY OF PICKERING AND REGION OF DURHAM STANDARDS, ONTARIO PROVINCIAL STANDARD DRAWINGS AND SPECIFICATIONS (OPSD & OPSS), THE WATER RESOURCES ACT, AND THE APPLICABLE ENVIRONMENTAL PROTECTION ACTS. WHERE A TOWN OR REGION STANDARD EXISTS, IT SHALL BE USED IN PLACE OF THE PROVINCIAL STANDARD. ALL WORK SHALL CONFORM TO THE APPLICABLE HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS.
- INFORMATION REGARDING ALL EXISTING UNDERGROUND UTILITIES AND SERVICES SHOWN ON THE DRAWINGS IS BASED ON INFORMATION PROVIDED BY OTHERS AND/OR AVAILABLE HISTORICAL DRAWINGS. THE ACCURACY OF THIS INFORMATION HAS NOT BEEN CONFIRMED BY KWA SITE DEVELOPMENT CONSULTING AND ALL UNDERGROUND INFORMATION NEEDS TO BE VERIFIED IN THE FIELD PRIOR TO BIDDING AND CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE TO ACQUIRE ALL UTILITY LOCATES PRIOR TO CONSTRUCTION AND TO NOTIFY THE ENGINEER OF ANY DISCREPANCIES. ANY LOST TIME DUE TO FAILURE TO IDENTIFY DISCREPANCIES OR NOTIFY THE ENGINEER SHALL BE AT THE CONTRACTOR'S EXPENSE.
- THIS PLAN SHOULD BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANT'S PLANS AND ANY DISCREPANCIES REPORTED TO THE ENGINEER PRIOR TO CONSTRUCTION.
- ALL DIMENSIONS SHALL BE CHECKED AND VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO ANY CONSTRUCTION AND ANY DISCREPANCIES REPORTED TO THE ENGINEER. INFORMATION REGARDING PRIVATE ROADS, PARKING LOT CURBS, BUILDING LOCATIONS, AND SETBACKS SHALL BE TAKEN FROM THE SITE PLAN.
- NO SUBSTITUTIONS SHALL BE ALLOWED WITHOUT ENGINEERS APPROVAL.
- ALL DISTURBED AREAS SHALL BE REPAIRED TO ORIGINAL CONDITION OR BETTER TO THE SATISFACTION OF THE ENGINEER.
- THE CONTRACTOR IS ADVISED THAT WORKS BY OTHERS MAY BE ONGOING AT THE SAME TIME AS THE CONTRACT. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES AND PREVENT CONSTRUCTION CONFLICTS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND PAYING FOR ALL PERMITS INCLUDING ROAD OCCUPANCY PERMITS AND THIRD PARTY UTILITY COSTS.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL TRAFFIC AND SAFETY MEASURES DURING THE CONSTRUCTION PERIOD, INCLUDING ALL NECESSARY SIGNALS, SIGNS, DELINEATORS, MARKERS AND BARRIERS. ALL TRAFFIC AND SAFETY MEASURES SHALL CONFORM TO CITY STANDARDS AND THE ONTARIO TRAFFIC MANUAL, BOOK 7 - TEMPORARY CONDITIONS, LATEST EDITION.
- THE CONTRACTOR SHALL COORDINATE ALL REQUIRED INSPECTIONS WITH THE CITY AND THE REGION AND ANY OTHER REGULATORY AGENCIES. ALL WORK ON TOWN OR REGION RIGHT-OF-WAY AND EASEMENTS, SEWER WORK, AND WATERMAIN WORK SHALL BE INSPECTED BY THE TOWN OR REGION (AS REQUIRED) PRIOR TO BACKFILLING.
- THE CONTRACTOR SHALL COORDINATE ALL REQUIRED INSPECTIONS WITH THE GEOTECHNICAL ENGINEER THROUGHOUT ENTIRE DURATION OF THE PROJECT.
- THE CONTRACTOR IS RESPONSIBLE TO INSTALL AND MAINTAIN EROSION AND SEDIMENT CONTROLS AS REQUIRED BY THIS CONTRACT AND TOWN AND PROVINCIAL STANDARDS.
- CONTRACTOR RESPONSIBLE TO SUPPLY AND INSTALL ALL NECESSARY CONSTRUCTION FENCING.
- CONTRACTOR TO PROVIDE WEEKLY REDLINE LINE AS-BUILT SURVEY TO THE ENGINEER FOR REVIEW. AS-BUILT TO SHOW PIPE INVERT, PIPE SIZE, AND PIPE MATERIAL.
- CONTRACTOR TO PROVIDE AS-BUILT SURVEY OF COMPLETED SERVICING AND GRADING WORKS INCLUDING INVERTS, ALL ABOVE GROUND WORKS AND SPOT ELEVATIONS AT MAXIMUM 15M GRID INTERVAL. SURVEY TO BE PREPARED BY LICENSED ONTARIO LAND SURVEYOR.
- DRAWING TO BE READ IN CONJUNCTION WITH THE GEOTECHNICAL INVESTIGATION REPORT PREPARED BY GEMTEC, DATED SEPTEMBER 30, 2025 AND ALL APPLICABLE ADDENDUMS.
- NO QUEUEING AND IDLING WILL BE ALLOWED.
- MATERIAL WILL NOT BE BROUGHT TO THE SITE OR LEAVE THE SITE THROUGH RESIDENTIAL AREAS AND ALL DISPOSAL MATERIAL WILL BE BROUGHT TO APPROVED AND LICENSED FACILITIES. DELIVERIES SHALL ARRIVE USING PROVINCIAL HIGHWAYS AND REGIONAL ROADS, AND STAGING SHALL BE DONE INTERNAL TO SITE WITHIN THE FUTURE PHASE LANDS AND WITHOUT IDLING OR QUEUEING ON EXTERNAL ROADS.

SPILL MANAGEMENT NOTES:

- NO STORAGE OF BULK FUELS OR CHEMICALS IS ALLOWED ON THE SUBJECT SITE.
- A SPILL CLEAN-UP PLAN MUST BE IN PLACE AND ALL SPILLS BE REPORTED TO THE MINISTRY OF ENVIRONMENT AND CLIMATE CHANGE SPILLS ACTION CENTRE.
- AN ON-SITE MANAGER SHALL BE DESIGNATED AS THE SPILL COORDINATOR AND SHALL CONDUCT REGULAR VISUAL INSPECTION TO IDENTIFY AREAS WITH OIL STAINING OR OTHER EVIDENCE OF ENVIRONMENTAL CONCERN (I.E. POOLS OF LIQUID, ODOURS, VAPOUR, ETC.).
- A SPILL KIT SHALL BE LOCATED WITHIN THE SITE TRAILER AND IN KEY VEHICLES CONTAINING ITEMS FOR PERSONAL PROTECTION AND SMALL SPILL CLEANUP. THE SPILL KIT SHALL ONLY BE USED BY TRAINED PERSONNEL AND THE SPILL MANAGER SHALL COMPLETE A KIT INVENTORY MONTHLY.
- IF A SPILL IS DETECTED THAT CANNOT BE CONTAINED SAFELY UTILIZING THE ON-SITE SPILL KIT, AN EVACUATION MUST TAKE PLACE AND THE SPILL COORDINATOR MUST CONTACT PICKERING FIRE SERVICES (AND THE OTHER EMERGENCY CONTACTS FOUND BELOW) IMMEDIATELY.
- SILT LADEN RUN OFF LEAVING THE SITE IS A REPORTABLE SPILL UNDER THE REGION OF DURHAM SEWER USE BY-LAW 55-2013, AS AMENDED, IN ADDITION TO PROVINCIAL AND FEDERAL LEGISLATION. ALL SPILL SPILLS THAT IMPACT A SEWER SYSTEM, WATER COURSE, OR CITY PROPERTY, MUST BE IMMEDIATELY REPORTED TO THE SPILLS ACTION CENTRE (1-800-268-6060).
- ALL SPILL MONITORING, INCIDENTS, AND CLEANUP SHALL BE DOCUMENTED INCLUDING (BUT NOT LIMITED TO): NAMES, DATES, TIME, LOCATION, DURATION (IF KNOWN), TYPE AND QUANTITY, SOURCE, ENVIRONMENTAL CONDITIONS, ACTIONS TAKEN, AGENCIES CONTACTED, AND FOLLOWUP COMPLETED.
- ANY AREAS OF CONCERN IDENTIFIED SHALL BE INVESTIGATED AS WOULD ANY SPILL BEFORE CONTACTING THE EMERGENCY CONTACTS LISTED BELOW.
- PRIOR TO DISCHARGE TO MUNICIPAL SEWERS FOR DE-WATERING A DISCHARGE AGREEMENT MUST BE APPROVED BY ENVIRONMENTAL SERVICES AS PER THE SEWER USE BY-LAW 55-2013.
- VEHICLE MAINTENANCE SHALL BE COMPLETED A MINIMUM OF 15m AWAY FROM ANY FUTURE INFILTRATION AREAS AND THE PROPOSED ESC POND.

LEGEND

- SLT — SLT — PROPOSED SILT FENCE
- 184.05 — PROPOSED CONTOUR
- 184.05 — EXISTING CONTOUR
- ROCK CHECK DAM
- PROPOSED INTERCEPTOR SWALE AND FLOW DIRECTION AS PER (OPSD 219.211)
- EXISTING SWALE TO REMAIN
- CONSTRUCTION ENTRANCE AS PER REGION OF DURHAM STANDARD S-301.050
- SILTSACK INLET SEDIMENT CONTROL DEVICE
- EXISTING STORM SEWER
- EXISTING STORM MANHOLE
- EXISTING CATCH BASIN
- LIMIT OF REGADING
- SWALE TRIBUTARY BOUNDARY

EMERGENCY CONTACTS	
FIRE/POLICE/AMBULANCE	911
CLIMATE CHANGE SPILL ACTION CENTRE	1-800-268-6060
MECP-SPILLS ACTION CENTRE	1 (416) 325-3000
CANUTEC (CANADIAN EMERGENCY CENTRE)	1 (813) 966-6666

24 HOUR CONTACTS:
 GRANARCO TAVANELLO 416-989-8104
 BRIAN TILLEY (416) 717-8319

REVISION BLOCK


#	DATE	DESCRIPTION
1	04/14/25	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA



KWA SITE DEVELOPMENT
 2455 Ashland Drive
 Burlington, ON L7R 7A9



NORTH ARROW




SURVEY AND BENCHMARK NOTE

EXISTING TOPOGRAPHIC INFORMATION SHOWN ON THIS PLAN ARE BASED ON J.D. BARNES LTD. DRAWING (REF. NO. 25-25-360-00), DATED AUGUST 20, 2020.

ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.
















METRIC SCALE



1:500

CONSTRUCTION MANAGEMENT PLAN
FIELDGATE COMMERCIAL
TAUNTON RD/BURKHOLDER DR.
 PICKERING, ONTARIO CITY OF PICKERING FILE FB 01-2025
 PROJECT NO. 23810 DRAWN BY: BS CHECKED BY: EJ

CMP




REVISION BLOCK

#	DATE	DESCRIPTION
1	04/14/23	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA



KWA SITE DEVELOPMENT
 2450 Appleton Drive
 Burlington, ON L7L 7A9



EXISTING TOPOGRAPHIC INFORMATION SHOWN ON THIS PLAN ARE BASED ON J.D. BARNES LTD. DRAWING (REF. NO. 25-25-300-00), DATED AUGUST 20, 2020.

ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.

METRIC SCALE
 N.T.S.


SITE DETAILS PLAN 1
 FIELDGATE COMMERCIAL
 TAUNTON RD/BURKHOLDER DR.
 PICKERING, ONTARIO

PROJECT NO. 2810 | DRAWN BY: BS | CHECKED BY: BJ



ELEVATED CATCHBASIN IN BIOSWALE

BIORETENTION MIX	
TOPSOIL	2 PARTS TOPSOIL
	3 PARTS SAND
	1 PART ORGANIC SOIL COMPONENTS
SOIL PARTICLE SIZE DISTRIBUTION	
SAND	75-90%
SILT	7-22%
CLAY	3-15%
GRAVEL	LESS THAN OR EQUAL TO 10%
PH	6.0-8.0
PLANT AVAILABLE NUTRIENT LEVELS	
PHOSPHORUS	
POTASSIUM	10-40
CALCIUM	80-250
MAGNESIUM	<5000
% ORGANIC	100-300

THE ABOVE BIORETENTION MIX HAS BEEN PREPARED USING THE CITY OF TORONTO CONSTRUCTION SPECIFICATION FOR GROWING MEDIUM AND THE SUSTAINABLE TECHNOLOGIES BIORETENTION FILTER MEDIA GUIDE. A SITE SPECIFIC MEDIA DESIGN SHALL BE PROVIDED BY THE LANDSCAPE ENGINEER OF RECORD TO ENSURE ALL SITE OBJECTIVES ARE MET.



GROUNDWATER ELEVATION ESTIMATED BASED ON FIELDGATE SEATON COMMUNITY DEVELOPMENT HYDRO-GEOLOGICAL STUDY OCTOBER 2023, BY GEMTEC SEE FIGURE B-6 FOR ESTIMATED GROUNDWATER CONTOURS, 168.40 FOR PROPOSED BIOSWALE




Tc-31R & Tc-31L




Rb-12 (600x600)mm

SIGN MOUNT LEGEND:
ALL SIGNS ARE SHOWN IN APPROXIMATE LOCATIONS AND TO BE DETERMINED ON SITE. SIGNS MUST BE VISIBLE TO DRIVER AND NOT OBSTRUCTED.


PROPOSED POST




TYPICAL V-NOTCH SWALE




TYPICAL FLAT-BOTTOM SWALE




SWALE UNDERDRAIN FOR FLAT BOTTOM SWALE




SWALE UNDERDRAIN FOR V-NOTCH SWALE




SUBDRAIN AT CATCHBASINS & CATCHBASIN MANHOLES



OUTLET CONTROL MANHOLE 8 DETAIL




OUTLET CONTROL MANHOLE 21 DETAIL



OUTLET CONTROL MANHOLE 22 DETAIL

REVISION BLOCK

#	DATE	DESCRIPTION
1	04/14/23	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA




SURVEY AND BENCHMARK NOTE
EXISTING TOPOGRAPHIC INFORMATION SHOWN ON THIS PLAN ARE BASED ON J.D. BARNES LTD. DRAWING (REF. NO. 25-25-300-00), DATED AUGUST 20, 2025.
ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.

METRIC SCALE
N.T.S.

SITE DETAILS PLAN 2
FIELDGATE COMMERCIAL
TAUNTON RD/BURKHOLDER DR.
PICKERING, ONTARIO
PROJECT No. 23810 | DRAWN BY: AS | CHECKED BY: BJ

REVISION BLOCK

#	DATE	DESCRIPTION
1	04/14/23	ISSUED FOR SPA
2	12/04/25	ISSUED FOR SPA



SURVEY AND BENCHMARK NOTE
 EXISTING TOPOGRAPHIC INFORMATIONS SHOWN ON THIS PLAN ARE BASED ON J.D. BARNES LTD. DRAWING (REF. NO. 25-25-300-00), DATED AUGUST 20, 2025.
 ELEVATIONS ARE GEODETIC AND ARE REFERRED TO CITY OF PICKERING VERTICAL.

METRIC SCALE
 AS NOTED

CHAMBER CROSS SECTIONS
 FIELDGATE COMMERCIAL
 TAUNTON RD/BURKHOLDER DR.
 PICKERING, ONTARIO
 PROJECT No. 23810 | DRAWN BY: AS | CHECKED BY: BJ

XSEC

